


NOTES:

1. INSPECTION MUST BE OBTAINED FOR SADDLE PRIOR TO BACKFILLING OVER LATERAL.
2. WHERE HOUSE LATERALS ARE TO BE JOINED TO EXISTING SEWERS THE CONNECTION SHALL BE MADE BY CUTTING INTO THE PIPE AND INSTALLING AN APPROVED SADDLE. THIS SADDLE TO BE ORDERED FOR THE PARTICULAR SIZE AND MATERIAL OF PIPE ON WHICH IT IS PLACED. THE SADDLE MUST BE FITTED SNUGLY AGAINST THE EXTERIOR WALL OF THE PIPE ON WHICH IT IS PLACED.
3. SADDLE SHALL BE ROMAC "CB" SEWER SADDLE OR APPROVED EQUAL. CONTRACTOR SHALL SUBMIT THE SADDLE INFORMATION AT THE TIME OF REQUESTING AN INSPECTION.
4. SADDLE TO BE INSTALLED PER MANUFACTURER'S INSTRUCTIONS.
5. AT CONNECTION TO EXISTING SEWER MAIN OF NOMINAL DIAMETER 15" OR GREATER, CONSTRUCT NEW MANHOLE PER SBMWD STANDARD DRAWINGS S.300 & S.301.



N.T.S.

REVISION	DATE	CITY OF SAN BERNARDINO MUNICIPAL WATER DEPARTMENT	DRAWING NUMBER
		SEWER SADDLE	SBMWD S.307
DRAWN BY: JRVS		APPROVED  DATE 07/03/2019	
SUPERVISED: EL			
WARREN HUANG, P.E. RCE 49208			